Pre-Backfill Digital Twin Documentation

For Maintenance and Inspection

Lucas Grein
Skywalker Drone Imagery LLC
Westminster, Colorado

Proceedings Paper
NOWRA Mega-Conference

Abstract

This paper introduces pre-backfill digital twin documentation as a supplemental project record created immediately prior to backfill. It defines the documentation approach, describes a practical workflow for creating the record, compares it with conventional documentation methods, and discusses applications that may support maintenance, inspection, communication, and long-term stewardship of onsite wastewater treatment systems.

1. Introduction

Documentation is a fundamental component of onsite wastewater treatment system (OWTS) design, installation, operation, and long-term management. Engineering plans, permits, inspection records, operation and maintenance documentation, and as-built records collectively establish the historical record of a system and provide information used by homeowners, installers, engineers, maintenance providers, inspectors, and regulatory agencies throughout its operational life. Although documentation requirements and practices vary among jurisdictions, the shared objective is to preserve an accurate record of the completed installation for future reference.

A unique opportunity for documentation exists during the period between completion of installation and backfill. At this stage, all system components remain exposed, allowing the complete installation—including component locations, spatial relationships, elevations, and surrounding site conditions—to be documented while still visible. Once backfill is complete, direct observation of these installed conditions is no longer possible, and future understanding of the system depends upon the records created during construction.

Advances in aerial imaging, photogrammetry, and geospatial data processing now make it practical to capture highly detailed documentation during this stage of construction. High-resolution orthomosaics, three-dimensional reconstructions, georeferenced measurements, and annotated imagery can be combined to create a comprehensive digital record of the completed installation before it is concealed.

This paper introduces the concept of pre-backfill digital twin documentation as a supplemental project record created immediately prior to backfill. It defines the documentation approach, describes a practical workflow for creating the record, compares it with conventional documentation methods, and discusses applications that may support maintenance, inspection, communication, and long-term stewardship of onsite wastewater treatment systems.

2. The Pre-Backfill Documentation Window

The installation of an onsite wastewater treatment system includes a brief period during which all system components remain fully exposed prior to backfill. Tanks, piping, distribution components, cleanouts, inspection ports, and other installed features can be observed in their final locations while their spatial relationships to one another and to surrounding site features remain clearly visible. This represents the only stage in the life of the system during which the completed installation can be viewed in its entirety.

Following backfill, the exposed installation is replaced by the documentation retained within the project record. Depending on jurisdictional requirements and project-specific practices, this documentation may include engineering plans, inspection reports, as-built records, photographs, measurements, field notes, and permit documentation. These materials become the primary reference for future maintenance, inspection, repair, modification, and regulatory review.

The pre-backfill stage provides an opportunity to supplement these traditional records with a comprehensive visual and geospatial representation of the completed installation. Rather than documenting individual components independently, the installation can be preserved as a single spatially referenced dataset that records component locations, dimensions, elevations, site context, and the relationships among system elements while they remain visible.

Because this opportunity occurs only once during construction, documentation created during the pre-backfill stage becomes a permanent record of conditions that cannot be directly recreated after the system has been concealed. As geospatial documentation technologies continue to mature, capturing this information has become increasingly practical and offers an additional means of preserving installation records for future reference.



Figure 1. The complete installation can be documented in a single overhead view while components remain exposed.

3. Defining Pre-Backfill Digital Twin Documentation

For the purposes of this paper, pre-backfill digital twin documentation is defined as a comprehensive visual and geospatial record of an onsite wastewater treatment system captured after installation is complete and immediately prior to backfill. Its purpose is to preserve the completed installation while all system components remain visible and accessible for documentation.

Unlike conventional documentation, which often consists of separate drawings, photographs, measurements, and written notes, pre-backfill digital twin documentation integrates multiple forms of information into a single spatially referenced record. Depending on project requirements, this record may

include high-resolution orthomosaic imagery, three-dimensional reconstruction, georeferenced measurements, annotated component locations, and supporting photographs or field documentation. Together, these elements provide both a measurable representation of the installation and a permanent visual record of constructed conditions.

Within this paper, the term digital twin refers specifically to this documented digital representation of the installed onsite wastewater treatment system at a single point in time. It does not describe a continuously updated operational model or a real-time monitoring system as the term is sometimes used in manufacturing or infrastructure management. Instead, it represents a permanent documentation record of the completed installation immediately before backfill.

Pre-backfill digital twin documentation is intended to complement—not replace—existing project documentation. Engineering plans communicate design intent, inspection records document regulatory review, and as-built records preserve the completed installation. The digital twin serves as an additional visual and spatial record that may improve long-term understanding of the installed system while remaining consistent with established documentation practices.



Figure 2. A three-dimensional reconstruction preserves site context and the spatial relationships among visible components.

4. Creating the Documentation Record

Pre-backfill digital twin documentation is created after installation has been completed and before backfill operations begin. At this stage, all installed components remain exposed, allowing the completed system to be documented in its final constructed condition. Documentation is performed before equipment, materials, or earthwork obscure the installation.

The documentation process begins with the collection of high-resolution aerial imagery that captures the entire installation and its relationship to surrounding site features. Image acquisition is planned with sufficient coverage and overlap to support the generation of both a high-resolution orthomosaic and a three-dimensional reconstruction. Depending on project objectives, additional positioning methods or ground control may be incorporated to improve spatial accuracy.

Following image acquisition, photogrammetric processing is used to generate the digital documentation products. The orthomosaic provides an accurate plan-view representation of the completed installation, while the three-dimensional model preserves site topography and the spatial relationships between system

components. Additional annotations may identify tanks, distribution components, piping, cleanouts, inspection ports, control panels, electrical components, and other project-specific features. Measurements, labels, supporting photographs, engineering drawings, and field notes may also be incorporated into the documentation package.




Figure 3. An elevation heat map adds measurable vertical context to the visual record.

The completed record may include orthomosaic imagery, three-dimensional models, annotated figures, supporting photographs, and archived project files. When maintained alongside engineering plans, permits, inspection reports, operation and maintenance documentation, and as-built records, these materials become part of the permanent project record and remain available throughout the operational life of the system.

5. Field Comparisons

The practical value of pre-backfill digital twin documentation is best understood by comparing it with documentation traditionally maintained throughout the lifecycle of an onsite wastewater treatment system. Although documentation requirements differ among jurisdictions, the following comparisons illustrate how supplemental visual and geospatial documentation may enhance the long-term project record without replacing existing documentation practices.

Engineering Design and Installed Conditions

Engineering plans communicate the intended design of an onsite wastewater treatment system prior to construction. During installation, however, field conditions may require adjustments that preserve the overall design intent while accommodating site-specific constraints encountered during construction.

Documentation captured immediately prior to backfill preserves the completed installation exactly as constructed. When reviewed alongside the engineering design, the documentation provides a visual comparison between design intent and completed construction while preserving the final location and orientation of installed components within the site. This relationship may provide valuable context during future maintenance, repairs, modifications, or system evaluations.

Traditional Documentation and Supplemental Documentation

Traditional project records commonly include engineering plans, inspection documentation, permits, photographs, and as-built records. Each serves a distinct purpose within the permanent project file and remains essential for documenting the design, regulatory review, and completed installation.

Pre-backfill digital twin documentation supplements these records by preserving a comprehensive visual and spatial representation of the completed system. Rather than replacing traditional documentation, it provides additional context by recording component locations, surrounding site features, spatial relationships, and measurable project conditions within a single georeferenced record.




Figure 4. Conventional paper records and a digital documentation package provide complementary views of the same installation.

Before and After Backfill

The completion of backfill marks the point at which direct observation of the installed system is no longer possible. Future maintenance, inspection, repair, and engineering decisions must therefore rely on the documentation retained as part of the permanent project record.

Documentation created immediately prior to backfill preserves installed conditions that cannot be directly recreated once construction has been completed. As a result, future stakeholders are able to reference the completed installation as it existed before concealment, providing visual context that may not be available through conventional documentation alone.

Collectively, these comparisons demonstrate that pre-backfill digital twin documentation is intended to complement established documentation practices by preserving visual and spatial information that may remain valuable throughout the operational life of the system.

6. Maintenance and Inspection Applications

The value of pre-backfill digital twin documentation extends beyond construction. Once archived as part of the permanent project record, the same documentation may support a variety of maintenance, inspection, engineering, regulatory, and ownership activities throughout the life of the onsite wastewater treatment system.

Maintenance providers frequently rely on existing project records to locate buried infrastructure and understand system configuration prior to excavation or troubleshooting. Supplemental visual documentation may improve understanding of component locations, spatial relationships, and surrounding site conditions before field work begins, particularly when systems have been operating for many years or have changed ownership.




Figure 5. Annotated imagery can preserve measurable relationships among pipes, components, and surrounding site features.

Inspection personnel may also benefit from documentation that preserves the completed installation immediately prior to backfill. While inspection reports document regulatory review during construction, supplemental visual documentation provides additional context that may assist future inspections, repairs, modifications, or replacement activities when the original installation is no longer visible.

Engineers and installers may reference the documentation when evaluating existing systems, designing modifications, or planning future site improvements. Engineering plans preserve design intent, while the supplemental documentation preserves completed construction. Together, these records provide a more complete understanding of the project as both designed and installed.

Regulatory agencies and local jurisdictions often maintain project records for decades. As digital record management systems continue to evolve, supplemental visual documentation may enhance existing permit

files by preserving a permanent geospatial record that remains available to future staff, property owners, engineers, installers, and maintenance providers.




Figure 6. A georeferenced pre-backfill record can remain available as a GIS layer long after the installation is concealed.

Homeowners may also benefit from improved documentation. A permanent visual record of the completed installation may assist property owners in understanding the general layout of their onsite wastewater treatment system, planning future landscaping or construction activities, and communicating with contractors performing work near buried infrastructure.

Although each stakeholder applies the documentation differently, the underlying record remains unchanged. A single documentation package may support maintenance, inspection, engineering review, regulatory record management, and homeowner understanding throughout the life of the system while complementing the traditional records already maintained for the project.

7. Practical Considerations

Pre-backfill digital twin documentation is intended to supplement existing project documentation and should be implemented with consideration for project objectives, documentation requirements, and long-term record management. As with any documentation method, the long-term value of the record depends on the quality of the information captured and its continued accessibility throughout the operational life of the system.

Timing is one of the most important considerations. Documentation must be completed after installation is finished and before backfill begins, requiring coordination with installers and construction schedules. Temporary site conditions, including construction equipment, stockpiled materials, standing water, or incomplete installation activities, may also influence the completeness of the documentation and should be considered during planning.

The appropriate level of documentation will vary among projects. System complexity, site characteristics, owner objectives, regulatory requirements, and anticipated long-term maintenance needs may all influence

whether supplemental documentation provides meaningful value. The documentation approach should be selected to meet the needs of the individual project rather than applied uniformly across all installations.

Long-term accessibility is equally important. The usefulness of any documentation depends not only on how it is created, but also on how it is stored, maintained, and retrieved. As documentation platforms and software continue to evolve, preserving source imagery and associated project data may improve the long-term usability of the record while maintaining compatibility with future technologies.

Ultimately, pre-backfill digital twin documentation should be viewed as one component of a comprehensive project record. Engineering plans, permits, inspection reports, operation and maintenance documentation, and as-built records each provide information that serves a specific purpose throughout the life of an onsite wastewater treatment system. Supplemental visual and geospatial documentation is most effective when integrated with these existing records to provide a more complete understanding of the completed installation.

8. Discussion

Documentation has long been central to the design, construction, operation, and long-term management of onsite wastewater treatment systems. Engineering plans, permits, inspection reports, operation and maintenance documentation, and as-built records each preserve different aspects of a project and collectively provide the information needed to support future maintenance, inspection, repair, and regulatory oversight. As methods for collecting and managing geospatial information continue to advance, additional forms of documentation may further strengthen the permanent project record.

Pre-backfill digital twin documentation represents one approach to preserving installed conditions immediately before they are concealed. Rather than replacing traditional documentation, it supplements the existing project record with a visual and spatial representation of the completed installation. When maintained alongside conventional documentation, this additional record may improve communication among project stakeholders while providing future reference during maintenance, inspection, system modification, and engineering evaluation.

The examples and applications presented in this paper illustrate that a single documentation record may serve multiple purposes throughout the life of an onsite wastewater treatment system. Engineers, installers, maintenance providers, inspectors, regulatory agencies, and property owners each interact with project documentation from different perspectives, yet all rely upon an accurate understanding of the completed installation. A comprehensive visual and geospatial record provides an additional resource that may improve that understanding while remaining consistent with established documentation practices.

Continued advances in geospatial imaging, data processing, and digital record management will likely expand the ways in which documentation can be created, preserved, and accessed.

Regardless of future technological developments, the underlying objective remains unchanged: to preserve accurate, accessible, and durable documentation that supports informed decision-making throughout the life of the system.

9. Conclusion

Pre-backfill digital twin documentation provides an opportunity to preserve visual and spatial information during a unique stage of onsite wastewater system installation. Captured after installation is complete and immediately before backfill, the documentation records installed conditions while all system components remain visible.

As discussed throughout this paper, pre-backfill digital twin documentation is intended to complement existing project documentation rather than replace it. Engineering plans, permits, inspection reports,

operation and maintenance documentation, and as-built records each fulfill established roles within the permanent project record. Supplemental visual and geospatial documentation provides an additional representation of the completed installation that may support maintenance, inspection, engineering review, regulatory record management, and homeowner understanding throughout the operational life of the system.

The documentation approach presented in this paper demonstrates how a single digital record may serve multiple stakeholders while preserving conditions that cannot be directly observed after construction has been completed. As documentation practices continue to evolve, pre-backfill digital twin documentation represents one practical example of how modern geospatial technologies can complement existing workflows while strengthening the long-term documentation of onsite wastewater treatment systems.