

initial backfill

Portion of an excavation above the haunch zone or bedding with a depth of 6-12 inches (15 to 30 cm) above the piping, conduit tank, or structure; see diagram at bedding.